

15TH LOK SABHA ANNEXURE IX – B SR. NO. 1 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of jetty towards Kharwawada, Vanakbara from South side of mouth creek i.e. opposite to Narani Sea Food Shop, Vanakbara for the length of 25 mtrs. (Under M.P.L.A.D. Scheme)

BUDGET HEAD	:	8443 – Civil Deposits III, 108 – P.W.D. deposits, 117 – Deposit for the works done for public bodies or private individuals.
HISTORY	:	The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for construction of dry dock platform / jetty by providing C.C. main wall with back earth filling and siling & C.C. pavement on top for landing, bearinging & beaching of vessels on Southern side of existing Jetty near Fisheries Godown at Vanakbara – Diu for a length of 25.00 mts. vide his letter No. MP/D & D/MPLADS/2009-10 dated 06-01-2010 (copy placed in file). Also, the Superintendent, Collectorate, Diu has suggested to prepare the estimate for above said work vide his letter ide his letter No. 19-1-96/ACCTS/MPLADS/2009-10/4040 dated 27-01-2010 (copy placed in file). Hence the estimate is prepared.
DESIGN & SCOPE	:	It is proposed to provide dry dock platform for a length of 2500 mts. along the creek and 40.00 mts. (avg.) width. It is proposed to provide C.C. 1:1 ½ 3 wall with 16 mm dia dowel bar at bottom & top with nominal reinforcement on top of C.C. main wall and providing W.S. bela masonry side wall. The concrete pavement with temperature reinforcement on top of platform. Also the items of earth filling and rubble stone soling on top of platform and 15 mm thick cement plaster for wall are considered in the estimate.
RATE	:	The estimate is prepared based on GSR of 2008-09 of R & B of Rajkot circle of Gujarat state and Rate Analysis based on Market rate.
COST	:	The estimate cost worked out of Rs. 24,96,400/-
ESTABLISHMENT	:	0.5 % contingencies charges have been included in the estimate.
TIME	:	120 days will be required to complete the work after issue of work order.
DATE OF ACTUAL STARTING OF WORK	:	14/12/2010
DATE OF ACTUAL COMPLETION OF WORK	:	23/01/2012

**(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.**

15TH LOK SABHA ANNEXURE IX – B SR. NO. 2 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Fisheries Jetty in Saudwadi, Diu (Under M.P.L.A.D. Scheme)

BUDGET HEAD	:	8443 – Civil Deposits III, 108 – P.W.D. deposits, 117 – Deposit for the works done for public bodies or private individuals.
HISTORY	:	The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for construction of dry dock platform / jetty by providing C.C. main wall with back earth filling and siling & C.C. pavement on top for landing, bearinging & beaching of vessels on Southern side of existing Jetty near Fisheries Godown at Vanakbara – Diu for a length of 25.00 mts. vide his letter No. MPLADS/D&D/2009-10 dated 07-02-2010 (copy placed in file). Also, the Superintendent, Collectorate, Diu has suggested to prepare the estimate for above said work vide his letter ide his letter No. 19-1-96/ACCTS/MPLADS/2009-10/4470 dated 25-02-2010 (copy placed in file). Hence the estimate is prepared.
DESIGN & SCOPE	:	It is proposed to provide dry dock platform for a length of 2500 mts. along the creek and 40.00 mts. (avg.) width. It is proposed to provide C.C. 1:1 ½ 3 wall with 16 mm dia dowel bar at bottom & top with nominal reinforcement on top of C.C. main wall and providing W.S. bela masonry side wall. The concrete pavement with temperature reinforcement on top of platform. Also the items of earth filling and rubble stone soling on top of platform and 15 mm thick cement plaster for wall are considered in the estimate.
RATE	:	The estimate is prepared based on GSR of 2008-09 of R & B of Rajkot circle of Gujarat state and Rate Analysis based on Market rate.
COST	:	The estimate cost worked out of Rs. 24,92,500/-
ESTABLISHMENT	:	0.5 % contingencies charges have been included in the estimate.
TIME	:	120 days will be required to complete the work after issue of work order.
DATE OF ACTUAL STARTING OF WORK	:	18/04/2012
DATE OF ACTUAL COMPLETION OF WORK	:	14/08/2012

**(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.**

15TH LOK SABHA ANNEXURE IX – B SR. NO. 3 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Fisherman Shed (Big) near Treatment Plant at Mahatra bunder Ghoghla-Diu Under MPLAD Scheme

- BUDGET HEAD** : 8443 – Civil Deposits III,
108 – P.W.D. deposits,
117 – Deposit for the works done for public bodies or private individuals.
- HISTORY** : The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for construction of Fisherman Shed (Big) near Treatment Plant at Mahatra bunder Ghoghla, Diu vide his letter No. MPLADS/D&D/2009-10/89 dated 21/03/2011 and letter No. MPLADS/D&D/2011-12 dated 06/01/2012 (Copies enclosed). Also, the Superintendent, Collectorate, Diu has suggested to prepare the estimate for above said work vide his letter No. 19-1-96/ACCTS/MPLADS/2011-12/3452 dated 17/01/2012 (Copy enclosed). Hence this proposal.
- DESIGN & SCOPE** : It is proposed to construct Fisherman Shed of A.C. Sheet roof shed of size 25.00 x 16.00 mts. The corrugated A.C. sheet of 6 mm thick roof will rest on the steel truss of I.S.A. angles and 200 mm dia G.I. pipe vertical post. The other required items of foundation concrete, C.C. flooring pavement, w.s. bela masonry anti-corrosive coating, oil painting and information board / granite plate & Pedestal etc. are considered in the estimate.
- RATE** : The estimate is prepared based on S.O.R. 2011-2012 of R & B of Rajkot circle of Gujarat state and Rate analysis based on G.S.R. have been considered for preparing the estimate.
- COST** : The estimate cost worked out of Rs. 21,94,560/-
- ESTABLISHMENT** : 0.5 % contingencies charges have been included in the estimate.
- TIME** : 90 days will be required to complete the work after issue of work order.
- DATE OF ACTUAL STARTING OF WORK** : 19/05/2012
- DATE OF ACTUAL COMPLETION OF WORK** : 20/10/2012

**(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.**

15TH LOK SABHA ANNEXURE IX – B SR. NO. 4 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Leveling and Improvement of area for beaching of vessels opposite Kharwawada at Vanakbara, Diu (Under MPLAD Scheme).

BUDGET HEAD : 8443 – Civil Deposits III,
108 – P.W.D. deposits,
80 – General,
117 – Deposit for the works done for public bodies or private individuals.

HISTORY : The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for leveling and Improvement of area for beaching of vessels opposite Kharwawada at Vanakbara under MPLAD Scheme vide his letter No. MPLADS/D&D/2011-12/508 dated 06/01/2012 (copy enclosed). Also, the Superintendent, Collectorate, Diu has suggested to prepare the estimate for above said work vide his letter No. 19-1-96/ACCTS/MPLADS/2012-13/2393 dated 31/10/2012 (copy enclosed). Hence this proposal.

DESIGN & SCOPE : It is proposed to develop beaching area by leveling of ground with providing earth filing, rubble filing, mentalling and rolling W.B.M. surface. The items of white stone bela masonry and plastering are also included in the estimate for raising of wall of existing open gutter.

RATE : The estimate is prepared based on S.O.R. rates of 2012-13 have been considered for preparing the estimate.

COST : The estimate cost worked out of Rs. 6,92,100/-

ESTABLISHMENT : 0.5 % contingencies charges have been included in the estimate.

TIME : 90 days will be required to complete the work after issue of work order.

DATE OF ACTUAL STARTING OF WORK : 27/02/2013

DATE OF ACTUAL COMPLETION OF WORK : 30/07/2013

**(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.**

15TH LOK SABHA ANNEXURE IX – B SR. NO. 5 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Compound wall and Providing Cement concrete interlocking paver block in Kabrastan at Ghoghla- Diu. Under MPLAD Scheme.

- BUDGET HEAD :**
- 8443 – Civil Deposits III,
 - 108 – P.W.D. deposits,
 - 80 – General,
 - 117 – Deposit for the works done for public bodies or private individuals.
- HISTORY :** The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for construction of compound wall and providing Cement concrete interlocking paver block in Kabrastan at Ghoghla- Diu under MPLAD Scheme vide his letter dated 06/01/2011 and letter No. MPLADS/D&D/2011-12/339 dated 30/06/2012 (copy enclosed). The Superintendent, Collectorate, Diu has suggested to prepare the estimate for above said work vide his letter No. 19-1-96/ACCTS/MPLADS/2011-12/2393 dated 17/04/2012 (copy enclosed). Hence this proposal.
- DESIGN & SCOPE :** It this estimate it is proposed to construct W.S.bela Masonary Compund wall on East side and North side for Kabrastan and Providing interlocking paver block on C.C. 1:3:6 base for approach roads and entrance chowk. The items of other allied works like M.S. gate, Cement plaster, water proofing Cement paint and white wash for wall are also included in the estimate.
- RATE :** The estimate is prepared based on S.O.R. 2012-13 of R & B of Rajkot Circle in Gujarat State, S.O.R. for port and Rate analysis based on S.O.R.
- COST :** The estimate cost worked out of Rs. 11,96,700/-
- ESTABLISHMENT :** 0.5 % contingencies charges have been included in the estimate.
- TIME :** 120 days will be required to complete the work after issue of work order.
- DATE OF ACTUAL STARTING OF WORK :** 27/02/2013
- DATE OF ACTUAL COMPLETION OF WORK :** 30/05/2013

**(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.**

15TH LOK SABHA ANNEXURE IX – B SR. NO. 6 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Fisherman Shed at Bunder jetty near Koliwada, Ghoghla-Diu (Under MPLAD Scheme).

BUDGET HEAD	:	8443 – Civil Deposits III, 108 – P.W.D. deposits, 80 – General, 117 – Deposit for the works done for public bodies or private individuals.
HISTORY	:	The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for construction of Fisherman Shed at Bunder jetty near Koliwada, Ghoghla-Diu. (Under MPLAD Scheme) vide his letter No. MPLADS/D&D/2011-12/575 dated 10/11/2012 (copy enclosed). Also, the Mamlatdar, H.O. Collectorate, Diu has suggested to prepare the estimate for above said work vide his letter No. 19-1-96/ACCTS/MPLADS/2012-13/2753 dated 10/12/2012 (Copy enclosed). Hence this proposal.
DESIGN & SCOPE	:	It is proposed to construct Fisherman Shed of A.C. Sheet roof shed of size 25.00 x 16.00 mts. The corrugated A.C. sheet of 6 mm thick roof will rest on the steel truss of I.S.A. angles and 200 mm dia G.I. pipe vertical post. The other required items of foundation concrete, soling, WBM and C.C. flooring pavement, w.s. bela masonry anti-corrosive coating, oil painting and information board / granite plate & Pedestal etc. are considered in the estimate.
RATE	:	The estimate is prepared based on S.O.R. 2012-2013 of R & B of Rajkot circle of Gujarat state and Market Rates are considered for preparing the estimate.
COST	:	The estimate cost worked out of Rs. 24,96,500/-
ESTABLISHMENT	:	5 % contingencies charges have been included in the estimate.
TIME	:	180 days will be required to complete the work after issue of work order.
DATE OF ACTUAL STARTING OF WORK	:	09/08/2013
STIPULATED DATE OF COMPLETION OF WORK	:	20/02/2014

**(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.**

15TH LOK SABHA ANNEXURE IX – B SR. NO. 7 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Aanganwadi Building and compound wall at Ganesh Nagar near C.H.C. at Ghoghla – Diu. (Under MPLAD Scheme)

BUDGET HEAD	:	8443 – Civil Deposits III, 108 – P.W.D. deposits, 80 – General, 117 – Deposit for the works done for public bodies or private individuals.
HISTORY	:	The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for Construction of Aanganwadi Building and compound wall at Ganesh Nagar near C.H.C. at Ghoghla – Diu. (Under MPLAD Scheme) vide his letter dated 06/01/2011 and letter No. MPLADS/D&D/2011-12/3547 dated 24/01/2012 (copy enclosed). Hence this proposal.
DESIGN & SCOPE	:	The proposal is for construction of frame structure with RCC columns, beams, lintel, chhajja, slab in M-200 grade concrete including providing wooden pile below foundation trenches. The item of w.s. bela masonry for foundation and super structure, ceramic tiles on flooring, IPS flooring, Provision for construction of compound wall and paver block inside the compound wall are also considered in the estimate.
RATE	:	The estimate is prepared based on S.O.R. 2012-13 of R & B of Gujarat State, Delhi Schedule of rate 2012-13 and Market Rates are considered for preparing the estimate.
COST	:	The estimate cost worked out of Rs. 20,27,700/-
ESTABLISHMENT	:	12.5 % Electrification charges and 0.5 % contingencies charges have been included in the estimate.
TIME	:	180 days will be required to complete the work after issue of work order.
DATE OF ACTUAL STARTING OF WORK	:	Waiting for foundation stone laying from the Hon'ble M.P. for commencement of work.

**(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.**

15TH LOK SABHA ANNEXURE IX – B SR. NO. 8 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Community Hall of Shree Valmiki Bhangi Harijan Samaj at Vekaria road, Diu. Under MPLAD Scheme.

- BUDGET HEAD** : 8443 – Civil Deposits III,
108 – P.W.D. deposits,
80 – General,
117 – Deposit for the works done for public bodies or private individuals.
- HISTORY** : The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for construction of Community Hall of Shree Valmiki Bhangi Harijan Samaj at Vekaria road, Diu, under MPLAD Scheme vide his letter No. MPLADS/D&D/2011-12/379 dated 20/07/2012 (copy enclosed). The H.O. Collectorate, Diu has also suggested to prepare an estimate for above said work vide his letter No. 19-1-96/ACCTS/MPLADS/2012-13/2021 dated 08/10/2012 (copy enclosed). Hence this proposal.
- DESIGN & SCOPE** : In this estimate it is proposed to construct community Hall on F.F. and G.F. is for open porch consisting of frame structure with R.C.C. columns, beams, lintel, chhajja, slab in M200 concrete including provision of 32 mm. dia dowel bars below rocky strata for footing foundation and R.C.C. staircase to access the F.F. hall. The items of W.S. Bela masonry for Super Structure at F.F. ceramic tiles in flooring & skirting on both the floors, inside / outside cement plastering work, painting to building by distemping for inside walls and water proofing cement paint for out side walls, G.I. pipe ladder and Sanitation Items are also included in the estimate.
- RATE** : The estimate is prepared based on S.O.R. 2012-2013 of R & B of Rajkot circle, Delhi Schedule of rate 2011-12, water supply S.O.R. 2011-12 of Gujarat state and rate analysis based S.O.R. and market rate have been considered for preparing an estimate.
- COST** : The estimate cost worked out of Rs. 24,78,600/-
- ESTABLISHMENT** : 0.5 % contingencies charges have been included in the estimate.
- TIME** : 180 days will be required to complete the work after issue of work order.

(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.

15TH LOK SABHA ANNEXURE IX – B SR. NO. 9 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Community Hall near Bus Stand at Ghoghla – Diu.(Under MPLAD Scheme).

- BUDGET HEAD** : 8443 – Civil Deposits III,
108 – P.W.D. deposits,
80 – General,
117 – Deposit for the works done for public bodies or private individuals.
- HISTORY** : The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for construction of community hall under MPLAD Scheme, near Bus Stand at Ghoghla – Diu, vide his letter No. DD/MPLADS/2011-12/371 dated 16/07/2012 (copy enclosed). The Superintendent, Collectorate, Diu has also suggested to prepare an estimate for above said work vide his letter No. 65-05-2010-LND/3245 dated 21/01/2013 (copy enclosed). Hence the estimate is prepared.
- DESIGN & SCOPE** : The proposed construction of community hall is of size 23.37 mt. x 10.46 mt., contains one hall, stage, dressing rooms, toilet and staircase at ground floor. The building will be RCC frame structure with columns, beams, lintel, chhajja, slab in M.200 grade concrete with provision of wooden pile below foundation footing. The item of W.S. bela masonry work, cement plastering, ceramic tiles on flooring, inside distempering exterior water proofing cement paint, M.S. Grill, Aluminum section window, flush door and sanitary & water supply items are considered for preparing estimate.
- RATE** : The estimate is prepared based on D.S.R. of 2012 at C.P.W.D., S.O.R. 2012-13 of R & B of Rajkot circle in Gujarat State are considered for preparing an estimate.
- COST** : The estimate cost worked out of Rs. 39,53,600/-
- ESTABLISHMENT** : 5 % contingencies charges have been added in the estimate.
- TIME** : 120 days will be required to complete the work after issue of work order.

(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.

15TH LOK SABHA ANNEXURE IX – B SR. NO. 10 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Community Hall in Pavti Bucharwada Group Gram Panchayat at Bucharwada – Diu.
Under MPLAD Scheme.

- BUDGET HEAD** : 8443 – Civil Deposits III,
108 – P.W.D. DEPOSITS,
PUBLIC BODIES OR PRIVATE INDIVIDUALS.
- HISTORY** : The Hon'ble M.P., Daman & Diu has requested to prepare an estimate for Construction of Community Hall in Pavti Bucharwada Group Gram Panchayat at Bucharwada – Diu. Under MPLAD Scheme, vide his letter No. MPLADS/D&D/2011-12/103 dated 05/03/2012 (copy enclosed). Hence this proposal.
- DESIGN & SCOPE** : The proposed construction of frame structure with columns, beams, lintel, chhajja, slab in M.200 grade concrete including providing and fixing mild steel dowel bars as the strata is rocky most of portion looking to the low lying of Ground area from the existing adjoining road, the building is proposed to be construct basement in half portion. Consisting toilet & bath block, kitchen and Dining Hall and on above basement it is proposed to construct a Hall, stage, additional rooms and staircase to access towards terrace on First Floor. The item of W.S.Bela masonry for foundation & super structure, ceramic tiles on flooring and walls, IPS flooring, alluminium sections for windows, flush doors, M.S. grill, Inside / Outside cement plaster, Distemping and water cement paint and provision for construction of compound wall with duratone tiles around setback area are also considered in the estimate.
- RATE** : The estimate is prepared based on S.O.R. 2012-2013 of R & B of Rajkot circle, Delhi Schedule of rate 2011-12, water supply G.M.B. S.O.R. 2011-12 of Gujarat state and rate analysis based S.O.R. and Market rate have been considered for preparing an estimate.
- COST** : The estimate cost worked out of Rs. 60,43,200/-
- ESTABLISHMENT** : 12.5 % for electrification and 0.5 % contingencies charges have been added in the estimate.
- TIME** : 180 days will be required to complete the work after issue of work order.

(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.

15TH LOK SABHA ANNEXURE IX – B SR. NO. 11 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Providing cement concrete pavement on Existing WBM work of platform near house of Mavji Vasram at Kharwada, Vanakbara – Diu. (Under MPLAD Scheme).

BUDGET HEAD	:	8443 – Civil Deposits III, 108 – P.W.D. deposits, 80 – General, 117 – Deposit for the works done for public bodies or private individuals.
HISTORY	:	The work of leveling of platform for beaching of vessels upto the soling stage is completed. The top surface of this platform is required to be provided by concrete pavement for its proper utilization for landing, berthing and beaching of vessels. The work is proposed under MPLAD Scheme by the Hon'ble M.P., Daman & Diu vide his letter dated 03/07/2013 and the H.O. Collectorate, Diu vide his letter No. 19-1-2013-14/MPLADS/DIU/2052, dated 12/08/2013 (copy placed in the file). Hence this estimate.
DESIGN & SCOPE	:	The proposed to provide base course of P.C.C. 1:3:6 over the existing soling surface. Over that finishing coat of C.C. 1: 1½:3 pavement of 10 cm thickness is proposed with temperature reinforcement. The items of filling of concrete joints is also considered in the estimate.
RATE	:	The estimate is prepared based on G.S.R. 2013-2014 of R & B & G.M.B. S.O.R. 2013-14 of Rajkot circle of Gujarat state and D.S.R. – 2012 of Delhi State have been considered for preparing an estimate.
COST	:	The estimate cost worked out of Rs. 8,29,200/-
ESTABLISHMENT	:	0.5 % contingencies charges have been added in the estimate.
TIME	:	90 days will be required to complete the work after issue of work order.

(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.

15TH LOK SABHA ANNEXURE IX – B SR. NO. 12 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Community Hall at Vanakbara, Diu. (Under MPLAD Scheme).

BUDGET HEAD : 8443 – Civil Deposits III,
108 – P.W.D. deposits,
117 – Deposit for the works done for public bodies or private individuals.

HISTORY : The Hon'ble Member of Parliament, Daman & Diu, Shri. Dahyabhai V. Patel, vide his letter No. MP/D&D/COL/MPLADS/2002/362 dated 03/10/2002 addressed to the Collector, Diu has requested for the above said work under the M.P.L.A.D. Scheme and the Collector Diu, vide his letter No. 19-1-96/2002-03/ACCT/MPLADS/5565 dated 08/12/2002, has requested to prepare the estimate of the above work. The site were inspected alongwith the coordinator, MPLADS, Vanakbara.

DESIGN & SCOPE : The proposed community hall will be constructed with RCC frame structure building with side gallery, terrazo tiles, flooring, non-teak wood doors and windows, all sanitary items, cement plaster works, inside, outside colour work and M.S. Windows grill also included in the estimate.

RATE : The rate based on G.S.R. 1999-2000 of Rajkot Circle and Market Rate.

COST : The estimate cost worked out of Rs. 14,91,130/-

ESTABLISHMENT : 5 % contingencies charges and 12.5 % Electrification charges have been included in the estimate.

TIME : days are required to complete the work after issue of work order.

DATE OF ACTUAL STARTING OF WORK : 03/09/2005

DATE OF ACTUAL COMPLETION OF WORK : 08/09/2006

(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.

15TH LOK SABHA ANNEXURE IX – B SR. NO. 13 WORK BRIEF

**Administration U.T. of Daman & Diu,
Office of the Executive Engineer,
Public Works Department,
Work Division – II,
Diu.**

Name of work : Construction of Jetty for landing and berthing of Passenger Ferry and fishing Vessels at Kob-Paj Bucharwada – Diu . (Under MPLAD Scheme).

BUDGET HEAD :

8443	–	Civil Deposits III,
108	–	P.W.D. deposits,
117	–	Deposit for the works done for public bodies or private individuals.

HISTORY : The Hon'ble M.P., Shri. Dahyabhai V. Patel has requested to construct a Jetty at Kob-Paj at Dagachi village vide his letter No. MP/D&D/COL/MPLAD/2001/192 dated 13/02/2001 and the Port Officer, Diu, vide his letter No. MD/PO-DIU/BUD/1-93/2000-01/1342 dated 01/03/2001 has requested to prepare the estimate and hence, the estimate is prepared under the M.P.L.A.D. Scheme for sanction of the same.

DESIGN & SCOPE : The proposal consisting of 138.00 Mt. long and 6.00 Mt. Wide Jetty towards Creek side, it is proposed 88.00 Mt. C.C. Wall on both the side towards Creek and 50.00 Mt. of masonry wall at approach side connecting the road. The space between two walls will be filled-up with selected soil and C.C. 1:3:6 base concrete and 50 mm thick C.C. flooring with nominal temperature reinforcement and R.C.C. 400 mm dia pipe for crossing of sea water also provided in the estimate.

RATE : The rate based on S.O.R. 1999-2000 of Rajkot Circle and Rate Analysis.

COST : The estimate cost worked out of Rs. 14,83,000/-

TIME : days are required to complete the work after issue of work order.

DATE OF ACTUAL STARTING OF WORK : 03/04/2005

DATE OF ACTUAL COMPLETION OF WORK : 28/09/2006

(C.A. Somani)
I/C Executive Engineer,
PWD, WD-II,
Diu.